



NORTHAW & CUFFLEY PARISH COUNCIL

7 Maynard Place, Cuffley, Herts, EN6 4JA
01707 875825

MEETING	Full Council
MEETING DATE	11 March 2026
SUBJECT	KGV Foul Sewer Run (Remedial works)
AGENDA ITEM NO.	2025-26 Item 69b
REPORT BY	Sally Griffiths, Office Manager, Northaw and Cuffley Parish Council

01 BACKGROUND:

Following new concerns raised regarding the sewer system at KGV, the Council commissioned a further CCTV survey of the foul sewer run at KGV in December 2025, with the results then compared to similar surveys carried out in July and October 2022 and April 2025.

The report from the Company was as follows:

"The survey identified various bulges within the pitch fibre sections of the pipework, multiple deformities, one circumferential crack within a clay pipe section, and multiple displacements. All displacements are falling in the correct direction and are therefore not affecting flow at this stage.

There are multiple standing water levels caused by bellied pipework within the runs, which can only be resolved through excavation works. A large proportion of the standing water is limited to short sections of approximately 1-2 metres.

We also identified a small amount of root ingress in the run between MH10 and MH11, entering through a connection and from the top of a joint; however, this is not currently affecting flow.

We were able to use the crawler unit to locate a downstream manhole beyond MH11, situated in the middle of the field. The root mass downstream of MH11 appears to reduce in size, allowing the crawler unit to pass through. We subsequently located the outfall manhole in the field, approximately 88 metres downstream of MH11. This line is flowing and contains a displacement that is not affecting flow.

We recommend excavation works between MH1 and MH3 due to the number of deformed sections within the pipework, as these have the potential to affect flow and cause blockages in the future.

SUMMARY

The condition of the drainage runs has deteriorated slightly, with bulges becoming more apparent and intrusive; however, no blockages were observed.

The pitch fibre sections between MH1-MH2 and MH2-MH3 show increased blistering and bulging, with the pipework deforming further.

Despite this, water continues to flow through these sections. We were able to push through to the large root mass present in the drainage run beyond the property within the field.

We can confirm that this is not currently affecting flow however increased paper build up and usage of the utilities blockages will become increasingly regular.

We have therefore obtained costs for the remedial works for the foul run.



NORTHAW & CUFFLEY PARISH COUNCIL

7 Maynard Place, Cuffley, Herts, EN6 4JA
01707 875825

02 PROPOSALS:

All contractors were sent the following requirements:

1) Remedial Works to Foul Run MH1- MH2:

To remove gates and posts from Football Club entrance before works can commence.

To excavate from MH2 in Football Club car park across driveway at entrance, upstream to a length of 10 metres to remove all deformed pitch fibre drainage pipe work.

To replace damaged pitch fibre pipe work with 100mm plastic and connect to existing pipe work at approximately 14.3 metres downstream from MH1 as shown on camera survey.

Backfill excavation and reinstate ground.

Reinstall gates and fence posts at Football Club entrance and reinstate concrete road with a strong mix concrete.

Remove all waste from site.

1) Remedial Works to Foul Run MH2- MH3

To excavate 31 metres of damaged pitch fibre pipe work to a depth of approximately 1 metre through tarmac.

Replace with new UPVC pipe work, back fill, reinstate with a concrete base and finish with hot roll tarmac.

We have been made aware by Contractors A & B that the above quoted works would take approx. 13-15 days, and then the ground will need to be left for a further 4 days before traffic would be allowed to drive on the re-laid driveway. This means that, if works were carried out, the entrance used by both the Bowls and Football Clubs may be unavailable for use for up to 3-4 weeks.

We have not investigated options to just reline the affected pipes, although this option was offered by one of the contractors.

Contractor A:

Remedial Works to Foul Run MH1- MH2:

Cost for works to include materials, plant & labour: £7,644.00 + vat

Remedial Works to Foul Run MH2- MH3

Does not include the application of hot roll tarmac, which would need to be done by alternative Contractors.

Cost for works to include materials, plant & labour: £12,940.00 + VAT

Contractor B:

Total for all required works (including hot roll tarmac) - £10,750.00 + VAT



NORTHAW & CUFFLEY PARISH COUNCIL

7 Maynard Place, Cuffley, Herts, EN6 4JA
01707 875825

Contractor C:

Total for all required works (excluding removing the gate and barrier) - £22,500.00 + VAT

Contractor C (Alternative solution offered):

Pitched fibre drain repairs Total £9,885.00

Please see the recommendations/cost to repair the mentioned pitched fibre drainage.

Contractor D:

No response to date.

03 DECISION REQUIRED FROM COUNCIL:

MOTION

Council resolves to proceed with remedial Foul Run works at KGV playing field, provided by their selected contractor, and that delegated authority be given to the Clerk to manage and oversee the project.

Implications (completed by the Clerk)	
Staffing Implications	Co-ordination, arrangement of works and overseeing, will be completed in normal working hours
Council objectives	Meets objectives
Equalities and human rights	There are no equality or human rights issues
Crime & Disorder	Crime and disorder have been considered
Biodiversity	There are no biodiversity issues
Financial	Decisions may give rise to additional expenditure from ear marked reserves
Legal	Local Government Act 1894, Section 8 (i) to execute any works (including works of maintenance or improvement) incidental to or consequential on the exercise of any of the foregoing powers, or in relation to any parish property, not being property relating to affairs of the church or held for an ecclesiastical charity;
Risk Management	Material risks exist and these will be assessed prior to works carried out. Insurances and all other documents from contractors will be retained